REGIONAL DISTRICT OF NANAIMO

REQUEST FOR TENDER No. 21-016

FCPCC Stage IV Expansion – Clearing and Grubbing

Addendum 2
(2 pages)

Issued: February 16, 2021

Closing Date & Time: on or before 3:00 PM Pacific Time on February 23, 2021

This addendum shall be read in conjunction with and considered as an integral part of the Request for Tender. Revisions supersede the information contained in the original Tender or previously issued Addendum. No consideration will be allowed for any extras due to any Vendor not being familiar with the contents of this Addendum. All other terms and conditions remain the same.

Clarifications:

1. Award of the contract is also dependent on completion and favourable outcome of bird nesting and habitat surveys by the RDN expected on or before March 8, 2021.
2. The existing chain link fence along the north side of the Existing Drying Beds (Dwg. C-1005) is to be removed and disposed of to outside the limits of clearing and grubbing.
3. The driveway bordering the west side of the work area is private property and is not to be used or traveled on for any reason.
4. Layout of the work area (i.e. limits of clearing and grubbing) is the responsibility of the Contractor. Area is clearly delineated on the drawings and via the table of trees which includes tree tags. The layout is to be reviewed by the Contractor with an RDN representative prior to work commencement.

Questions & Answers:

Q1) There is existing irrigation in the area of the treed berm and proposed access road to the west of the treed berm. How should this irrigation be treated?

A1) The existing irrigation is abandoned and can be left in place. Confirm with RDN that irrigation is disconnected and capped prior to commencing work in this area.

Q2) Can the trees on the berm outside the clearing and grubbing area shown on drawing C-1005 be removed for access, if needed?

A2) No trees are to be removed outside the area of clearing and grubbing identified on drawing C-1005.

Q3) Should the merchantable timber be left full length or bucked? If bucked, please provide specifications.

A3) Timber shall be limbed and cut to full length (16.1m or 13.4m, depending on length and diameter of tree). Large cedar trees (greater than approx. 20cm diameter) are to be cut to full length and stacked separately.

End of Addendum 2