REQUEST FOR TENDER No. 21-008

WCWSA Production Well Site Construction

Addendum 3
(2 pages)

Issued: March 1, 2021

Closing Date & Time: on or before 3:00 PM Pacific Time on March 4, 2021

1. Enclosed is Addendum 3 from the Project Engineer, MPE Engineering Ltd.

2. Reminder:

   Bidders must supply with their Tenders a **verifiable digital Bid Bond (e-bond) and a verifiable digital Consent of Surety** as defined by the Surety Association of Canada. Scanned copies are not acceptable.

   https://suretycanada.com/SAC/Surety-Bonds/E-Bonding.aspx

End of Addendum 3

Addendum # 3

To the Contract Specifications and Drawings for:
Regional District of Nanaimo
#21-008 WCWSA Production Well Site

MPE Engineering Ltd.
Suite 320, 6715 – 8 Street NE
Calgary, AB T2E 7H7

March 1, 2021

File: 9794-003-00

1. Precedence

This Addendum forms an integral part of the Contract Specifications and Drawings covering all aspects of this job and is to be read in conjunction therewith. However, should points arise which are at variance, this Addendum shall take precedence, unless otherwise clarified by the Engineer.

2. Purpose

This addendum provides specific clauses to add to and/or amend the specifications and/or drawings.

3. Drawing P14.1 – Process Well Details

Clarification: Pitless Adapter to be carbon steel coated with NSF-61 epoxy, in place of 304 Stainless Steel as indicated on the drawing. MAASS model with water tight cap MBHDS-1012.

Add: *"Note 10. The existing steel casing is 508 mm diameter. The Contractor is to modify the existing casing with a concentric reducer to suit a smaller 10" epoxy coated carbon steel Pitless Adaptor. All carbon steel welds to be coated with NSF-61 epoxy inside and outside. The Pitless Adaptor must suit a 75 mm bushing for the raw water feed line."*

END OF ADDENDUM